



Art Metal Workshop Inc.
18-50 PAXMAN ROAD
ETOBICOKE ON M9C 1B7
(416)848-4588
contact@art-metal.ca
GST/HST Registration No.: 876476607RT0001

Estimate 5938

ADDRESS John Gwozdowski	DATE 17/09/2018	TOTAL \$36,032.99	
-----------------------------------	---------------------------	-----------------------------	--

ACTIVITY	QTY	RATE	TAX	AMOUNT
Juliette Balcony 42" Height as per Ontario Building Code. Welding as per Canadian Welding Bureau standards. All welds are polished with grinder.	24	1,328.65	HST ON	31,887.60
Hot Dip Galvanizing To prevent rusting the steel/iron is submerged in a bath of molten zinc until it reaches 840 F (449 C). At this point, the zinc reacts with the steel to form zinc/iron intermetallic layers on all surfaces inside and out.	1	0.00	HST ON	0.00
Warranty Limited Lifetime Warranty for Galvanized steel products: Valid for exterior projects only. Not applied if damaged, removed or reinstalled. We guarantee our products not to rust for the period of at least 7 years if Hot Dip Galvanizing was purchased.	1	0.00	Exempt	0.00
Black Paint Finish FreshStart white primer for galvanized steel. Red oxide primer for non galvanized steel. Solignum commercial grade oil base flat black finish. All applications are sprayed in the workshop.	1	0.00	HST ON	0.00

35% deposit required to start the project.
Balance due on the day of installation.
Average to larger projects turnaround time is 6- 8 weeks on average. The turn around time varies on the season.
Ask us about financing your project.

cost of scissor lift and any installation costs to be determined on site

SUBTOTAL	31,887.60
HST (ON) @ 13%	4,145.39

TOTAL	\$36,032.99
-------	--------------------

THANK YOU.

Accepted By

Accepted Date

35% deposit required to start the project.
Balance due on the day of installation.
Average to larger projects turnaround time is 6- 8 weeks on average. The turn around time varies on the season.
Ask us about financing your project.